



DATA SHEET
Agenda Item No. 16.

Meeting Date: April 6, 2017

Agenda Item:

Ratify Emergency Change Order No. 2 in contract with Felix Construction Company in the amount of \$28,922.56 for added repairs found to be necessary in sedimentation basins at the Taylor Water Treatment Plant.

Placement:	<input checked="" type="checkbox"/> Consent	<input type="checkbox"/> Individual Consideration	<input type="checkbox"/> Executive Session
Vote:	<input checked="" type="checkbox"/> Non-Weighted	<input type="checkbox"/> Weighted Capital	
Recommending Department: Engineering			

Background:

At the April 7, 2016 meeting, the Board authorized award of contract for Basin Foundation Improvements at the Taylor RWTP to Felix Construction Company. During work within three of the plant sedimentation basins, extensive cracks in the concrete floors were discovered, along with an active leak. The cracks were allowing water to seep through the basins' reinforced concrete floor slabs. Water seepage in reinforced concrete exposes the steel to the corrosion process and undermines the bedding material under the slab. With the water demands increasing due to the warm weather, and the need to return the basins back into service as soon as possible, these cracks were authorized to be immediately repaired. An emergency change order was issued to Felix Construction Company in the amount of \$28,922.56 for crack sealant and repair. These repairs have been completed and the basins are currently in service.

Financial:

Sufficient funds are available in the FY 2017 Operating Budget for the Regional Treated Water System for this change order.

Recommendation:

That the Board of Directors ratify the emergency change order issued to Felix Construction Company in the amount of \$28,922.56 for added repairs found to be necessary in sedimentation basins at the Taylor WTP.

Enclosures:

For more information, please contact Jody Zabolio at (972) 219-1228.

Submitted By: _____

A handwritten signature in blue ink, appearing to read "Jody Zabolio".

Jody Zabolio, Acting Director/ Engineering & Construction

Date: March 31, 2017